

## **KEYNOTES**

- OPENING IN DRYWALL TO BE FINISHED AND CENTRE PIVOTING CLOSURE PIECE TO BE INSERTED. SEE DETAILS.
- (2) 50  $\times$  50 MM CERAMIC TILE AND CERAMIC BASE.
- 3 CUSTOM BOOKCASES AND CABINET. SEE MILLWORK. MEASURE ON SITE.
- (4) FINISHED FLOORS TO BE WIDE PLANK PINE FLOOR. RUN PLANKS PARALLEL TO GRID D
- 5) FINISHED FLOOR TO BE DETERMINED BY CLIENT
- (6) 3 TREADS @ 225MM MEASURE ON SITE.
- (7) 610 x 610 MM ACCESS HATCH FOR LIMITED STORAGE ABOVE
- 8 STEEL GUARD RAIL 915MM HIGH SEE DETAILS
- 9 PRE-MANUFACTURED CHIMNEY SEE DWG. A4.1
- (10) TILE WALLS IN SHOWER AREA. REPLACE GYPSUM WITH CEMENT BOARD
- (11) SHOWER FIXTURE(S) TO BE MOUNTED ON WALL AS REQUIRED
- (12) LINE OF CANOPY SHELTER BELOW. SEE DETAILS

- (3) LINE OF SUNSHADE ABOVE. SEE DETAILS
- (14) WODDEN GUARD RAIL 1070 IN HEIGHT
- 16 TREADS @ 225MM MEASURE ON SITE

## WALL TYPES

WT1 - 12.7MM GYPSUM, 38×140 WOOD STUDS, AIR/VAPOR BARRIER, GLASS FIBRE INSULATION, 7.5MM PLYWOOD OR OSB SHEATHING, METAL SIDING

WT2 - 12.7MM GYPSUM, 38×89 WOOD STUDS, 12.7MM GYPSUM



Ν